SECTION 260519 - LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

Latest Update: 06.04.2020 See Underlined Text for Edits

(Engineer shall edit specifications and blue text in header to meet project requirements. This includes but is not limited to updating Equipment and/or Material Model Numbers indicated in the specifications and adding any additional specifications that may be required by the project. <u>Also turn off "Underlines".</u>)

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this section and all other sections of Division 26.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Building wires and cables rated 600 V and less.
 - 2. Connectors, splices, and terminations rated 600 V and less.
 - 3. Sleeves and sleeve seals for cables.

1.3 DEFINITIONS

- A. EPDM: Ethylene-propylene-diene terpolymer rubber.
- B. NBR: Acrylonitrile-butadiene rubber.

1.4 SUBMITTALS

- A. General: Submit the following according to the Conditions of the Contract and Division 1 Specification Sections.
- B. Product Data: For each type of product indicated.
- C. Qualification Data: For testing agency.
- D. Field quality-control test reports.
- E. Operation and Maintenance materials.

1.5 QUALITY ASSURANCE

- A. Testing Agency Qualifications: An independent agency, with the experience and capability to conduct the testing indicated, that is a member company of the InterNational Electrical Testing Association or is a nationally recognized testing laboratory (NRTL) as defined by OSHA in 29 CFR 1910.7, and that is acceptable to authorities having jurisdiction.
 - 1. Testing Agency's Field Supervisor: Person currently certified by the InterNational Electrical Testing Association or the National Institute for Certification in Engineering Technologies to supervise on-site testing specified in Part 3.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- C. Comply with NFPA 70.

1.6 COORDINATION

A. Set sleeves in cast-in-place concrete, masonry walls, and other structural components as they are constructed.

1.7 WARRANTY/GUARANTEE

A. See Division 26 Specification Section "Basic Electrical Requirements' for warranty and guarantee requirements.

PART 2 - PRODUCTS

2.1 CONDUCTORS AND CABLES

- A. Manufacturers: Subject to compliance with requirements, provide products by one (1) of the following:
 - 1. Alcan Products Corporation; Alcan Cable Division.
 - 2. American Insulated Wire Corp.; a Leviton Company.
 - 3. General Cable Corporation.
 - 4. Senator Wire & Cable Company.
 - 5. Southwire Company.
 - 6. The Okonite Company.
 - 7. Belden, Inc.

- B. Copper Conductors: Comply with NEMA WC 70.
- C. Conductor Insulation: Comply with NEMA WC 70 for Types THHN-THWN and XHHW.
- D. Multiconductor Cable: Comply with NEMA WC 70 for steel-clad cable, Type MC with ground wire.
 - 1. Fittings: Steel
- E. Type MC cable for branch circuit applications
 - 1. Interlocking galvanized steel armor, steel strip.
 - 2. Conductor insulation THHN/THWN solid copper, 90 degree rated.
 - 3. Copper insulated green grounding conductor.
 - 4. Polyester assembly tape.
 - 5. Neutral conductor.
 - 6. Rated for use in plenums.
 - 7. Rated for through penetration of 1, 2, and 3-hour fire walls.
 - 8. UL 83, 1479, 1569, 1581, and 2556 listed.
 - 9. NEC 230.43, 250.118, 300.22, 392, 396, 330, 501, 502, 503, 530, 504, 505, 518, 530, 645, 725, 760, 760.154(A) compliant
 - 10. AFC Type MC, MC-Tuff Lightweight Steel

F. Fire Alarm Control Cable Type MC

- 11. For use on fire alarm circuits as required and as recommended by the manufacturer.
- 12. Interlocking galvanized steel armor, steel strip (painted red).
- 13. Conductor insulation TFN/THHN solid copper.
- 14. Copper grounding conductor.
- 15. Polyester assembly tape.
- 16. Neutral conductor.
- 17. UL Listed Fire Alarm Cable.
- 18. Rated for use in plenums.
- 19. Rated for through penetration of 1, 2, and 3-hour fire walls.
- 20. Individual twisted pairs and shielding, as required per fire alarm system manufacturer.
- 21. UL 66, 83, 1424, 1569, 1581, and 2556 listed.
- 22. NEC 300.22, 362, 330, 430.2, 501, 502, 503, 530, 504, 505, 518, 530, 645, 725, 760, 760.154(A) compliant
- 23. AFC Type MC Fire Alarm/Control Cable.
- G. Color Coding:

| 208/120 Volts | | 480/277 Volts | |
|---------------|-------|---------------|-------|
| Phase | Color | Phase | Color |
| А | Black | А | Brown |

| В | Red | В | Orange |
|---------|-------|---------|--------|
| С | Blue | С | Yellow |
| Neutral | White | Neutral | Gray |
| Ground | Green | Ground | Green |

2.2 CONNECTORS AND SPLICES

- A. Manufacturers: Subject to compliance with requirements, provide products by one (1) of the following:
 - 1. AFC Cable Systems, Inc.
 - 2. Hubbell Power Systems, Inc.
 - 3. O-Z/Gedney; EGS Electrical Group LLC.
 - 4. 3M; Electrical Products Division.
 - 5. Tyco Electronics Corp.
- B. Description: Factory-fabricated connectors and splices of size, ampacity rating, material, type, and class for application and service indicated.

2.3 SLEEVES FOR CABLES <u>AND SOUND PROOF PARTITIONS</u>

- A. Steel Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, galvanized steel, plain ends.
- B. Cast-Iron Pipe Sleeves: Cast or fabricated "wall pipe," equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop, unless otherwise indicated.
- C. Sleeves for Rectangular Openings: Galvanized sheet steel with minimum 0.052- or 0.138-inch thickness as indicated and of length to suit application.
- D. Coordinate sleeve selection and application with selection and application of firestopping specified in Division 07 Section "Penetration Firestopping."

2.4 SLEEVE SEALS

- A. Basis-of-Design Product: Subject to compliance with requirements, provide a comparable product by one (1) of the following:
 - 1. Advance Products & Systems, Inc.
 - 2. Calpico, Inc.
 - 3. Metraflex Co.
 - 4. Pipeline Seal and Insulator, Inc.

- B. Description: Modular sealing device, designed for field assembly, to fill annular space between sleeve and cable.
 - 1. Sealing Elements: NBR interlocking links shaped to fit surface of cable or conduit. Include type and number required for material and size of raceway or cable.
 - 2. Pressure Plates: Stainless steel. Include two for each sealing element.
 - 3. Connecting Bolts and Nuts: Stainless steel of length required to secure pressure plates to sealing elements. Include one for each sealing element.

PART 3 - EXECUTION

- 3.1 CONDUCTOR MATERIAL APPLICATIONS
 - A. Feeders: Copper. Solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.
 - B. Branch Circuits: Copper. Solid for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.
- 3.2 CONDUCTOR INSULATION AND MULTICONDUCTOR CABLE APPLICATIONS AND WIRING METHODS
 - A. Service Entrance: Type XHHW, single conductors in raceway.
 - B. Exposed Feeders: Type THHN-THWN, single conductors in raceway.
 - C. Feeders Concealed in Ceilings, Walls, Partitions, and Crawlspaces: Type THHN-THWN, single conductors in raceway.
 - D. Feeders Concealed in Concrete, below Slabs-on-Grade, and Underground: Type XHHW, single conductors in raceway.
 - E. Feeders Installed below Raised Flooring: Type THHN-THWN, single conductors in raceway or steel-clad cable, Type MC.
 - F. Exposed Branch Circuits, Including in Crawlspaces: Type THHN-THWN, single conductors in raceway.
 - G. Branch Circuits Concealed in Ceilings, Walls, and Partitions: Type THHN-THWN, single conductors in raceway or steel-clad cable, Type MC.
 - H. Branch Circuits Concealed in Concrete, below Slabs-on-Grade, and Underground: Type XHHW, single conductors in raceway.

- I. Branch Circuits Installed below Raised Flooring: Steel-clad cable, Type MC.
- J. Branch Circuits in Cable Tray: Type THHN-THWN, single conductors in raceway or steel-clad cable, Type MC.
- K. Cord Drops and Portable Appliance Connections: Type SO, hard service cord with stainless-steel, wire-mesh, strain relief device at terminations to suit application.
- L. Class 1 Control Circuits: Type THHN-THWN, in raceway.
- M. Class 2 Control Circuits: Type THHN-THWN, in raceway.

3.3 INSTALLATION OF CONDUCTORS AND CABLES

- A. Conceal cables in finished walls, ceilings, and floors, unless otherwise indicated.
- B. Use manufacturer-approved pulling compound or lubricant where necessary; compound used must not deteriorate conductor or insulation. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.
- C. Use pulling means, including fish tape, cable, rope, and basket-weave wire/cable grips that will not damage cables or raceway.
- D. Install exposed cables parallel and perpendicular to surfaces of exposed structural members, and follow surface contours where possible.
- E. Support cables according to Division 26 Section "Hangers and Supports for Electrical Systems."
- F. Identify and color-code conductors and cables according to Division 26 Section "Identification for Electrical Systems."
- G. MC Cable Installation Requirements:
 - 1. Install in compliance with NFPA 70.
 - 2. Locations: In dry wall partitions and above accessible ceilings. Do not install in masonry partitions or walls.
 - 3. Independently support all MC Cable runs; do not piggy-back on plumbing/HVAC, lighting fixture, and/or ceiling grid supports.
 - 4. Do not bundle more than three (3) runs together for supporting purposes.
 - 5. MC cable shall be installed in a neat and orderly fashion using batwings type supports.
 - 6. Minimum bend radius shall be as recommended by the manufacturer.
 - 7. MC cable run to switches shall have a neutral conductor.
 - 8. Cable larger than #8AWG shall not be permitted.

- 9. All acceptable homeruns from panels in electrical rooms shall be installed in EMT conduit to a junction box/wire trough outside electrical rooms in accessible ceiling of corridor.
- 10. Homeruns from panelboard to junction box outside of electrical room: wire in EMT or IMC raceway.
- 11. Do NOT run MC Cable in exposed locations (e.g. all open ceiling locations, Mechanical and Electrical Equipment Rooms, IT Rooms, etc.).
- 12. MC cable shall be secured at intervals not exceeding six (6) feet and within twelve (12) inches of every outlet box or fitting. Luminaire whips may be six (6) feet maximum without support.

3.4 CONNECTIONS

- A. Tighten electrical connectors and terminals according to manufacturer's published torquetightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.
- B. Make splices and taps that are compatible with conductor material and that possess equivalent or better mechanical strength and insulation ratings than unspliced conductors.
- C. Wiring at Outlets: Install conductor at each outlet, with at least 12 inches of slack.

3.5 SLEEVE INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Coordinate sleeve selection and application with selection and application of firestopping specified in Division 07 Section "Penetration Firestopping."
- B. Concrete Slabs and Walls: Install sleeves for penetrations unless core-drilled holes or formed openings are used. Install sleeves during erection of slabs and walls.
- C. Use pipe sleeves unless penetration arrangement requires rectangular sleeved opening.
- D. Rectangular Sleeve Minimum Metal Thickness:
 - 1. For sleeve rectangle perimeter less than fifty (50) inches and no side greater than 16 inches, thickness shall be 0.052 inch.
 - 2. For sleeve rectangle perimeter equal to, or greater than, fifty (50) inches and one (1) or more sides equal to, or greater than, sixteen (16) inches, thickness shall be 0.138 inch.
- E. Fire-Rated Assemblies: Install sleeves for penetrations of fire-rated floor and wall assemblies unless openings compatible with firestop system used are fabricated during construction of floor or wall.

- F. <u>Non-Fire-Rated Sound Proof Partition Penetrations: Where new and existing conduits</u> pass through interior partitions with sound proofing provide a pipe sleeves. Seal the annular spaces between construction openings, the sleeves, and conduits with sound proof insulation material equal to the width of the opening. The sound proof insulation shall match the insulation in the partition.
- G. Cut sleeves to length for mounting flush with both wall surfaces.
- H. Extend sleeves installed in floors three (3) inches above finished floor level.
- I. Size pipe sleeves to provide 1/4-inch annular clear space between sleeve and cable unless sleeve seal is to be installed or unless seismic criteria require different clearance.
- J. Seal space outside of sleeves with grout for penetrations of concrete and masonry and with approved joint compound for gypsum board assemblies.
- K. Interior Penetrations of Non-Fire-Rated Walls and Floors: Seal annular space between sleeve and cable, using joint sealant appropriate for size, depth, and location of joint according to Division 07 Section "Joint Sealants."
- L. Fire-Rated-Assembly Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at cable penetrations. Install sleeves and seal with firestop materials according to Division 07 Section "Penetration Firestopping."
- M. Roof-Penetration Sleeves: Seal penetration of individual cables with flexible boot-type flashing units applied in coordination with roofing work.
- N. Aboveground Exterior-Wall Penetrations: Seal penetrations using sleeves and mechanical sleeve seals. Size sleeves to allow for one (1) inch annular clear space between pipe and sleeve for installing mechanical sleeve seals.
- O. Underground Exterior-Wall Penetrations: Install cast-iron "wall pipes" for sleeves. Size sleeves to allow for one (1) inch annular clear space between cable and sleeve for installing mechanical sleeve seals.

3.6 SLEEVE-SEAL INSTALLATION

- A. Install to seal underground exterior-wall penetrations.
- B. Use type and number of sealing elements recommended by manufacturer for cable material and size. Position cable in center of sleeve. Assemble mechanical sleeve seals and install in annular space between cable and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.

3.7 FIRESTOPPING

A. Apply firestopping to electrical penetrations of fire-rated floor and wall assemblies to restore original fire-resistance rating of assembly according to Division 07 Section "Penetration Firestopping."

3.8 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections and prepare test reports.
- B. Perform tests and inspections and prepare test reports.
- C. Tests and Inspections:
 - 1. After installing conductors and cables and before electrical circuitry has been energized, test service entrance and feeder conductors, and conductors feeding the following critical equipment and services for compliance with requirements.

a.
<Insert, in separate subparagraphs, critical equipment and services to be tested.>

- 2. Perform each visual and mechanical inspection and electrical test stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.
- 3. Infrared Scanning: After Substantial Completion, but not more than sixty (60) days after Final Acceptance, perform an infrared scan of each splice in cables and conductors No. 3 AWG and larger. Remove box and equipment covers so splices are accessible to portable scanner.
 - a. Follow-up Infrared Scanning: Perform an additional follow-up infrared scan of each splice eleven (11) months after date of Substantial Completion.
 - b. Instrument: Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.
 - c. Record of Infrared Scanning: Prepare a certified report that identifies splices checked and that describes scanning results. Include notation of deficiencies detected, remedial action taken and observations after remedial action.
- D. Test Reports: Prepare a written report to record the following:
 - 1. Test procedures used.
 - 2. Test results that comply with requirements.

- 3. Test results that do not comply with requirements and corrective action taken to achieve compliance with requirements.
- E. Remove and replace malfunctioning units and retest as specified above.

END OF SECTION 260519